

# APPROVED

OCT 21 2021

## BOARD OF RECREATION AND PARK COMMISSIONERS

**BOARD REPORT**

NO. 21-178

DATE October 21, 2021

C.D. 4

### BOARD OF RECREATION AND PARK COMMISSIONERS

SUBJECT: GRIFFITH PARK – LA SHARES BUILDING DEMOLITION (PRJ21500) PROJECT – COMMITMENT OF PARK FEES – STATUTORY EXEMPTION FROM THE PROVISIONS OF THE CALIFORNIA ENVIRONMENTAL QUALITY ACT (CEQA) PURSUANT TO PUBLIC RESOURCES CODE SECTION 21080(b)(4) AS A SPECIFIC ACTION NECESSARY TO PREVENT OR MITIGATE AN EMERGENCY

AP Diaz	_____	M. Rudnick	_____
H. Fujita	_____	<i>for</i> C. Santo Domingo	<u>DF</u>
J. Kim	_____	N. Williams	_____

  
\_\_\_\_\_  
General Manager

Approved   X   Disapproved \_\_\_\_\_ Withdrawn \_\_\_\_\_

### RECOMMENDATIONS

1. Approve the scope of work of the Griffith Park - LA Shares Building Demolition (PRJ21500) Project (Project), as described in the Summary of this Report;
2. Authorize Department of Recreation and Parks (RAP) staff to commit from the following fund and work order numbers, a maximum of Four-Hundred Thousand Dollars (\$400,000.00) in Park Fees, for the proposed Project;

<u>FUNDING SOURCE</u>	<u>FUND/DEPT./ACCT. NO.</u>	<u>WORK ORDER NO.</u>
Park Fees	302/89/89718H	QZ900160
Park Fees	302/89/89716H	QT067577

3. Approve the proposed Project to be bid and constructed through RAP's list of pre-qualified on-call contractors;
4. Approve the authorization of change orders as authorized under Board Report #No. 06-136, for the construction contracts for this Project in the budget contingency amounts for such construction contracts as set forth in this Report;
5. Determine that the project is statutorily exempt from the provisions of the California Environmental Quality Act (CEQA) pursuant to Public Resources Code Section

## BOARD REPORT

PG. 2 NO. 21-178

21080(b)(4) as a specific action necessary to prevent or mitigate an emergency and direct RAP staff to file a Notice of Exemption (NOE) with the Los Angeles County Clerk;

6. Authorize RAP's Chief Accounting Employee to prepare a check to the Los Angeles County Clerk in the amount of \$75.00 for the purpose of filing an NOE; and,
7. Authorize RAP staff to make technical corrections as necessary to carry out the intent of this Report.

### SUMMARY

Griffith Park is located at 4730 Crystal Springs Drive in the Hollywood community of the City. This 4,281.73-acre park provides a variety of recreational programs and activities for the local community. Due to the size of the park, and the facilities, features, programs, and services it provides, Griffith Park meets the standards for a Regional park, as defined in the City's Public Recreation Plan.

### PROJECT SCOPE

The LA Shares building is located at 3210 Riverside Drive in Griffith Park. This building was built in the early 1960's and once served as the Costume Workshop for the Griffith Park Children's Theater. For many years the building has been occupied by L.A. SHARES, a nonprofit material reuse program that receives donations of reusable goods and materials and redistributes them free-of-charge to nonprofits and schools throughout the City. The building was damaged by fires that occurred in August 2020 and in September 2021.

The proposed Project includes the following scope of work items:

- Abatement and demolition of the fire damaged LA Shares building.
- Additional site work.
- Installation of new landscaping to replace the building site.

### PROJECT FUNDING

Upon approval of this Report, Four-Hundred Thousand Dollars (\$400,000) in Park Fees can be committed to the proposed Project.

The anticipated pre-qualified on-call contracts for this Project will be for Park Facility Construction. The budget contingency for the Park Facility Construction contracts will be Forty Thousand Dollars (\$40,000.00).

These Park Fees were collected within ten (10) miles of Griffith Park, which is the standard distance for the commitment of the Park Fees for regional recreational facilities pursuant to Los Angeles Municipal Code Section 12.33 E.3.

BOARD REPORT

PG. 3 NO. 21-178

FUNDING SOURCE MATRIX

<b>Source</b>	<b>Fund/Dept/Acct</b>	<b>Amount</b>	<b>Percentage</b>
Park Fees	302/89/89718H	\$48,266.36	12%
Park Fees	302/89/89716H	\$351,733.64	88%
<b>Total</b>		\$400,000.00	100%

PROJECT CONSTRUCTION

RAP Staff has determined that sufficient funding has been identified and the proposed Project is anticipated to begin in Fall 2021.

TREES AND SHADE

The proposed Project will have no impact on existing trees and shade at the park.

ENVIRONMENTAL IMPACT

The proposed project consists of the demolition of an existing building damaged by fires that occurred on August 20, 2020, September 14, 2021, and September 16, 2021 and the installation of new landscaping.

According to the attached Structural and Fire Assessment report (Attachment 2), this existing building cannot be feasibly repaired, reused, or rehabilitated. Since the structure was built in the 1960's, the structure is not likely to meet the current code requirements specifically for vertical and seismic lateral analyses. Therefore, the existing undamaged portions are not acceptable for today's building code. Because of the excessive fire damage in addition to termite dry rot damage, most of the building components are structurally compromised and will need to be demolished due to safety concerns.

Public Resources Code (PRC) section 21080(b)(4) provides that CEQA does not apply, to "specific actions necessary to prevent or mitigate an emergency." PRC section 21060.3 defines *emergency* as "a sudden, unexpected occurrence, involving a clear and imminent danger, demanding immediate action to prevent or mitigate loss of, or damage to, life, health, property, or essential public services." Section 21060.3 further provides that *emergency*, "includes such occurrences as fire, flood, earthquake, or other soil or geologic movements, as well as such occurrences as riot, accident, or sabotage."

The proposed project is an action that both prevents and mitigates an emergency. In fact, by demolishing an unsafe building that could collapse on park patrons, is a specific action necessary to prevent an emergency. Further, it mitigates the effects of multiple emergencies, the multiple

## BOARD REPORT

PG. 4 NO. 21-178

fires that occurred on August 20, 2020, September 14, 2021, and September 16, 2021 which compromised the structures of the building.

Therefore, staff recommends that the Board of Recreation and Park Commissioners (Board) determine that this Project is statutorily exempt from the provisions of the California Environmental Quality Act (CEQA) pursuant to Public Resources Code Section 21080(b)(4) as a specific action necessary to prevent or mitigate an emergency. Staff will file a NOE with the Los Angeles County Clerk upon the Board's approval.

### FISCAL IMPACT

The approval of the commitment of Park Fees will have no fiscal impact on RAP's General Fund.

The estimated costs for the actions listed in the Project Scope section of this report are anticipated to be funded by Park Fees or funding sources other than the RAP's General Fund. The maintenance of the proposed park improvements can be performed by current staff with minimal impact to existing maintenance service at this facility.

### STRATEGIC PLAN INITIATIVES AND GOALS

Approval of this Board Report advances RAP's Strategic Plan by supporting:

**Goal No. 1:** Provide Safe and Accessible Parks


**Outcome No. 2:** All parks are safe and welcoming

**Result:** The demolition of the fire damaged LA Shares Building will increase safety and enhance the park users' experience.

This report was prepared by Ajmal Noorzayee, Management Assistant, Planning, Maintenance and Construction Branch.

### LIST OF ATTACHMENTS

- 1) Map of location of LA Shares Building
- 2) Structural and Fire Assessment



L. A. SHARES

Cars And Coffee  
Los Angeles

Griffith Park Adult  
Community Center  
Temporarily closed

Friendship Auditorium

Leno/Rosemary  
LaBianca House

Eaves Los Feliz

Archstone Los Feliz

Ricky's Fish Tacos  
Takeout

Original Roadhouse Grill  
Office (no restaurant)

Google

# Technical Memorandum

---

**Date:** October 11, 2021

**To:** Elena Maggioni, City of Los Angeles, Department of Recreation and Parks

**From:** Victor Ramirez, SE – Tetra Tech, Geoffrey Heinen, EIT – Tetra Tech, Alexis Bahou, PE (Tetra Tech)

**Project:** LA SHARE Building

**Project Number:** 112G-SBA-T41752

**Subject:** Structural And Fire Assessment

---

## INTRODUCTION

The City of Los Angeles, Department of Recreation and Parks (RAP), received a Notice of Violation from the City of Los Angeles Department of Building and Safety (LADBS) on September 17, 2021. The Notice was regarding an abandoned office building located at 3224 Riverside Drive, near the Griffith Park. This existing structure is an old RAP office that was heavily damaged by three fires within the last few years. RAP requested that Tetra Tech perform a structural and fire assessment of the existing building. The goal of the assessment was to determine whether the structure could be repaired and rehabilitated, or whether the building should be demolished due to safety hazard. The structure is currently red-tagged and is closed off to the public by the LADBS. RAP contracted Tetra Tech to perform a visual inspection and determine the structural integrity of the building. Therefore, this Technical Memorandum has been prepared to describe the current condition of the building, include preliminary structural calculations, and recommend either demolition or replacement.

## BACKGROUND

The existing structure was built in the early 1960's for RAP to be near Griffith Park. The structure was occupied for many years before the 2020 pandemic. The structure is also included as a historical character-defining feature/contributing within the Historic-Cultural Monument (HCM) determination for Griffith Park. The roof of the structure has wood sheathing and framing and wood columns and bearing walls designed to support the roof. The structure contains multiple structural wood shear walls that act as the main seismic load resisting system. The existing building was damaged by fires that occurred on August 20, 2020, September 14, 2021, and September 16, 2021. As a result, the structure has been closed (red-tagged) until a structural and fire assessment could be performed under the direction of RAP.

## STRUCTURAL AND FIRE ASSESSMENT

Prior to the structural assessment, a Health and Safety Plan was prepared to cover emergency situations that might arise during the field investigation. On October 28, 2021, Geoff Heinen, a structural engineering designer, and Eric Hutchins, a Health Safety Officer, of Tetra Tech performed a structural assessment of existing building. During the field work, it was observed that RAP was able to create clear paths/walkways as part of hazardous building material abatement activities which allowed access to portions of the building while minimizing safety concerns.

During the structural assessment, Tetra Tech located the likely origin of the fire and its path due to the amount of damage inside. The ignition point started on the western side and spread to the eastern side of the existing building. This is evident from the extensive fire damage on the western side versus the eastern side of the building. The western side was completely burned while the eastern side was scarred by smoke. The fire traveled throughout the structure by the existing wooden roof. Old dry wood is an excellent fuel for fires especially in warmer climates. During the site visit, Tetra Tech provided a photo log to document any damaged structural components (See Appendix 1).

The roof and its columns were the only exposed structural components that were heavily damaged by these fires. Most of the building was protected by the fire-protected cementitious-material boards which are attached to the bearing walls. By observation, these cementitious-material boards prevented the entire structure from burning down and cause collapse (See Photo 40, 41 and 42). During the site visit, Tetra Tech examined critical structural components of the building. These structural components included the roof framing, columns, bearing walls and floor framing. As-built drawings were not available; therefore, Tetra Tech measured and recorded the dimensions, height and spacings of structural components which provided sufficient information to perform a limited structural analysis. An evaluation of each one of these structural components and the limited structural analysis is further described below.

- Tetra Tech visually inspected and assessed the current conditions of the existing wooden roof planks and beams. By observation, most of existing roof was heavily damaged from these fires especially on the western side of the building (See Photos 22 and 23). The existing roof components include asphaltic roof tiles, microfiber sheets, plywood and 2x5 wood planks. These roof components were supported by 4x10 wood beams which are the main support beams in the building. All these components are seen in each section of the building. Therefore, this is a typical design concept within this building. On the western side and center of the building, the surfaces of these wood planks and beams were heavily burnt. Additionally, there is evidence of termite damage within these planks and beams which further affects the structural integrity of the roof (See Photo 28). On the eastern side, the roof was not as heavily burnt but scarred to a dark gray color from the smoke. Like the western side, there is evidence of termite damage due to the wood fibers falling from the roof (See Photo 21). Because of the abandonment of this building and unknown structure maintenance, the termite damage may be much worse than what was observed in the field.

To further evaluate the current roof condition, preliminary structural calculations were completed to determine the wood plank and beam capacities before and after the fire. These structural calculations are included in this memo (See Appendix 2). When fire burns wooden structural components, the wood is either completely or partially burned. When the wood components are partially burned, structural members are reduced in size and load bearing capacity. During roof examination, there is evidence that the wood was partially burned by the fire. This evidence can be seen by how the burned beams are preventing the existing roof from collapsing completely. Due to safety concerns, Tetra Tech was not able to spot check for dry rot or determine the burnt thickness using steel probes on the wood roof planks and beams. Therefore, these calculations assume at a 1/2-inch of wood was partially burnt and indicate the roof support's capacity has been reduced to the point that workers cannot safely stand on the roof top due to the risk of collapse. The roof had collapsed in three areas of the building as observed on the western side (See Photo 45). Because of the reduced capacity of the structure, it is likely the roof will collapse due to its own weight, wind loads, or additional weight from rainwater. Therefore, the roof wood structural components will need to be demolished because of the high possibility of collapse.

---

- After the examining the roof, Tetra Tech visually inspected and assessed the current conditions of the existing wooden columns. Like the roof, the fire damage occurred mainly on the western side and then decreased on the eastern side. The columns have a 4" x 4" square shape and are spaced 47-inches throughout the building. These columns supported the vertical loads from the roof. Because of the fire, the size of columns and the associated axial capacity for each column member have been reduced. Due to safety reasons, Tetra Tech was not able to spot check for dry rot or determine the burnt thickness using steel probes on the columns. According to the current wood design and construction code, all structural members must meet a specific slenderness ratio to withstand buckling pressures. This slenderness ratio is critical because it prevents the structural member from having local fractures along its segment due to axial loading. Since the fire reduced the size of the columns, these existing columns will not meet this code requirement. On the eastern side of the building, the columns appeared to be in good condition but are scarred to a dark gray color from the smoke (See Photo 20). On the western side and center of the building, the columns were heavily damaged and have a charcoal-like texture. Tetra Tech found areas where there are missing structural columns, columns with missing segments, and columns with major structural cracks especially on the western side of the building (See Photos 43 and 47). These columns are extremely concerning because they increase the possibility of large roof sections collapsing. Therefore, all columns will need to be demolished because of the high possibility of collapse.
- The other vertical support system of the building includes the wooden bearing walls. Like the columns, these bearing walls are spaced evenly throughout the building, but they are less frequent than the columns. These walls are a system of multiple vertical posts and horizontal purlins. This system is used to transfer all vertical loading to the concrete foundation. These bearing walls also act to resist seismic shear. The shear walls were identified by the nails and fasteners that connect to the roof (See Photo 24) and by the anchored hold-down that connects the shear walls to the concrete foundation (See Photo 37). Due to the age of the building, it is most likely that the existing structure does not meet today's seismic code requirements. Because of this, Tetra Tech did not perform a limited seismic analysis of the structure. However, these walls are critical to the structural integrity in a seismic event. In the areas where the fire was less excessive, the walls are in good condition due the surrounding cementitious-material boards and their distance from the source of the fire (See Photo 35 and 38). In the areas where the fire was excessive, the cementitious-material boards were unable to protect bearing walls (See Photo 32 and 44). Like the columns, the structural members within the wall have a size reduction in capacity due to the fire. Because this structure is a roof wood flexible diaphragm, these shear walls will resist seismic loads due to the tributary weight of the roof. If one of the resistant members is compromised, the adjacent shear walls will need to resist more seismic load than anticipated due the increased tributary width. Because of this, the seismic demand may exceed the allowable capacities of the remaining shear walls.

Another critical portion of this seismic resistance is the shear transfer connection between the roof and wall. The purpose of this shear transfer is to translate all seismic loading due to roof and columns to the main seismic lateral resisting system which are the existing shear walls. During the site visit, the shear transfer fasteners appear to be in good condition. However, they will not adequately transfer the seismic load because of the burnt portions of the wood. The existing building's connection are connected by nails embedded into the wood. Since the fire reduced the size of these wood members, the embedded lengths of the nails are shortened. Because of this, the nail and fastener capacities are reduced and will make the shear transfer connection nonexistent. Therefore, the damaged bearing walls will need to be demolish due to a reduction in capacity and non-compliance with current code requirements.

- After examining the walls, Tetra Tech found that the exterior rooms have a raised wooden floor supported by wooden beams which extend outside of the building (See Photo 12). These raised floors appeared to be elevated 1-foot maximum above the existing concrete surface (See Photo 16). As-built drawings were not available; therefore, the true elevation of the raised floor from the concrete surface is unknown. The floor material was determined using a tapping technique with a hammer. Tapping on a concrete slab will make a quick and dull sound while a wood platform will make a hollow sound. Tetra Tech could not fully assess the conditions of the wood floor due to the debris covering the floor and safety hazards. However, a structural assessment was performed of the raised floor support beams extending outside of the building. By observation, these beams show evidence of termite damage and dry rot due to years of outside exposure. During the examination, some of the beams were completely rotted away (See Photos 13 and 14). If further termite damage and dry rot occurs, the beams will continue to lose load bearing capacity and possibly cause floor collapse. Due to access limitations, Tetra Tech does not know if fire damage occurred under the raised floor. However, like the wood roof, the raised floor was exposed with no additional fire protections. Therefore, it is likely the raised floor and its supports are structurally compromised and must be demolished due a lack of structural integrity.

Based on the completed structural and fire assessment, Tetra Tech concludes that this existing building cannot be feasibly repaired, reused, or rehabilitated. Since the structure was built in the 1960's, the structure is not likely to meet the current code requirements specifically for vertical and seismic lateral analyses. Therefore, the existing undamaged portions are not be acceptable for today's building code. Because of the excessive fire damage in addition to termite dry rot damage, most of the building components are structurally compromised and will need to be demolish due to safety concerns. Because of these concerns, Tetra Tech recommends RAP demolish the existing structure.


---

# Appendix 1


# PHOTOGRAPH LOG



**Photo 1: Exterior Western Portion of Building**



**Photo 2: Exterior Western Portion of Building**




**Photo 3: Rotting Wood Beam of Raised Floor On Western Portion of Building**

<p>Date: 03/18/2021</p>	<p>Project #: 112G-SBA-T41752</p>	<p>Project: LA SHARE Building</p>	
-----------------------------	---------------------------------------	---------------------------------------	---


# PHOTOGRAPH LOG



**Photo 4: Existing Hole at Bottom of Building.**



**Photo 5: Rotting Wood Beams for Raise Floor**



**Photo 6: Rotting Wood Beams for Raise Floor**

Date:  
03/18/2021

Project #:  
112G-SBA-T41752

Project:  
LA SHARE Building




# PHOTOGRAPH LOG



**Photo 7: Exterior Eastern Portion of Building w/ Burned Rooftop**



**Photo 8: Rotting Wood Beam of Raised Floor On Western Portion of Building**



**Photo 9: Burned Rooftop**

<p>Date: 03/18/2021</p>	<p>Project #: 112G-SBA-T41752</p>	<p>Project: LA SHARE Building</p>	
-----------------------------	---------------------------------------	---------------------------------------	---

# PHOTOGRAPH LOG



**Photo 10: Rotten Wood Beam for Raised Floor**



**Photo 11: Exterior Portion of Building**



**Photo 12: Exterior Eastern Portion of Building w/ Rotten Wooden Beams**

<p>Date: 03/18/2021</p>	<p>Project #: 112G-SBA-T41752</p>	<p>Project: LA SHARE Building</p>	
-----------------------------	---------------------------------------	---------------------------------------	---


# PHOTOGRAPH LOG



**Photo 13: Rotten Wood Beam**



**Photo 14: Burned Wood Joist for Raised Floor**



**Photo 15: Exterior Eastern Portion of Building**

<p>Date: 03/18/2021</p>	<p>Project #: 112G-SBA-T41752</p>	<p>Project: LA SHARE Building</p>	
-----------------------------	---------------------------------------	---------------------------------------	---

# PHOTOGRAPH LOG



**Photo 16: Exterior Supports of Raised Floor**



**Photo 17: Burned Rooftop and Framing**



**Photo 18: Burned Posts in Rooftop**

<p>Date: 03/18/2021</p>	<p>Project #: 112G-SBA-T41752</p>	<p>Project: LA SHARE Building</p>	
-----------------------------	---------------------------------------	---------------------------------------	---

# PHOTOGRAPH LOG



Photo 19: Smoked-Scarred Room



Photo 20: Typical Beam to Column Connection




Photo 21: Typical Wood Beam

Date:  
03/18/2021

Project #:  
112G-SBA-T41752


Project:  
LA SHARE Building



# PHOTOGRAPH LOG



**Photo 22: Burned Roof and Beams**



**Photo 23: Burned Interior Column**



**Photo 24: Shear Transfer from Roof to Shear Wall**

<p>Date: 03/18/2021</p>	<p>Project #: 112G-SBA-T41752</p>	<p>Project: LA SHARE Building</p>	
-----------------------------	---------------------------------------	---------------------------------------	---

# PHOTOGRAPH LOG



**Photo 25: Burned Interior Columns at Western Side**



**Photo 26: Beam to Column Connection**



**Photo 27: Burned Interior Columns at Western Side**

Date:  
03/18/2021

Project #:  
112G-SBA-T41752

Project:  
LA SHARE Building




# PHOTOGRAPH LOG



**Photo 28: Interior Column and Beam  
w/ Size Reduction**



**Photo 29: Burned Beams at Building  
Center**



**Photo 30: Burned Interior Columns at  
Building Center**


Date:  
03/18/2021

Project #:  
112G-SBA-T41752

Project:  
LA SHARE Building



# PHOTOGRAPH LOG



**Photo 31: Interior Bearing / Shear Wall**



**Photo 32: Damaged Portion of Bearing / Shear Wall**




**Photo 33: Burned Gypsum Board on Wall**

<p>Date: 03/18/2021</p>	<p>Project #: 112G-SBA-T41752</p>	<p>Project: LA SHARE Building</p>	
-----------------------------	---------------------------------------	---------------------------------------	---


# PHOTOGRAPH LOG



**Photo 34: Burned Post of Shear Wall**




**Photo 35: Exposed Portion of Wall w/  
Termite Damage**



**Photo 36: Typical Interior Bearing /  
Shear Wall**

<p>Date: 03/18/2021</p>	<p>Project #: 112G-SBA-T41752</p>	<p>Project: LA SHARE Building</p>	
-----------------------------	---------------------------------------	---------------------------------------	---


# PHOTOGRAPH LOG



**Photo 37: Typical Hold-down Seismic Connection**



**Photo 38: Undamaged Bearing / Shear Wall**



**Photo 39: Gypsum Board Interior**

Date:  
03/18/2021

Project #:  
112G-SBA-T41752

Project:  
LA SHARE Building



# PHOTOGRAPH LOG



**Photo 40: Coating Spalling due to Fire**



**Photo 41: Coating Spalling due to Fire**



**Photo 42: Coating Spalling due to Fire**

Date:  
03/18/2021

Project #:  
112G-SBA-T41752

Project:  
LA SHARE Building



# PHOTOGRAPH LOG



**Photo 43: Cracked Interior Column due to Fire**



**Photo 44: Heavily Burned Interior Support Wall**



**Photo 45: Roof Opening due to Collapse**


Date:  
03/18/2021

Project #:  
112G-SBA-T41752


Project:  
LA SHARE Building



# PHOTOGRAPH LOG



**Photo 46: Burned Interior Wall Post**



**Photo 47: View of Most-Compromised Building Section**



**Photo 48: Damaged Portion of Wall**

<p>Date: 03/18/2021</p>	<p>Project #: 112G-SBA-T41752</p>	<p>Project: LA SHARE Building</p>	
-----------------------------	---------------------------------------	---------------------------------------	---

## Appendix 2

Project Title:  
 Engineer:  
 Project ID:  
 Project Descr:

## Wood Beam

File: ENERCALC.ec6  
 Software copyright ENERCALC, INC. 1983-2020, Build:12.20.8.24  
 TETRA TECH INC

Lic. #: KW-06002149


DESCRIPTION: Typical Roof Beam (Before Fire)

### CODE REFERENCES

Calculations per NDS 2018, IBC 2018, CBC 2019, ASCE 7-16  
 Load Combination Set : ASCE 7-16

### Material Properties

Analysis Method : Allowable Stress Design	Fb +	1,500.0 psi	E : Modulus of Elasticity
Load Combination : ASCE 7-16	Fb -	1,500.0 psi	Ebend- xx
	Fc - Prll	1,700.0 psi	Eminbend - xx
Wood Species : Douglas Fir-Larch	Fc - Perp	625.0 psi	
Wood Grade : Select Structural	Fv	180.0 psi	
	Ft	1,000.0 psi	Density
Beam Bracing : Completely Unbraced			31.210pcf



### Applied Loads

Service loads entered. Load Factors will be applied for calculations.

Uniform Load : D = 0.0080, Lr = 0.020 ksf, Tributary Width = 8.0 ft. (DL + LL)

### DESIGN SUMMARY

**Design OK**

Maximum Bending Stress Ratio =	<b>0.900</b> : 1	Maximum Shear Stress Ratio =	<b>0.347</b> : 1
Section used for this span	<b>4x10</b>	Section used for this span	<b>4x10</b>
fb: Actual =	1,832.77 psi	fv: Actual =	78.12 psi
Fb: Allowable =	2,036.82 psi	Fv: Allowable =	225.00 psi
Load Combination	+D+Lr+H	Load Combination	+D+Lr+H
Location of maximum on span	8.250ft	Location of maximum on span	0.000ft
Span # where maximum occurs	Span # 1	Span # where maximum occurs	Span # 1
<b>Maximum Deflection</b>			
Max Downward Transient Deflection	0.612 in	Ratio =	323 >=180
Max Upward Transient Deflection	0.000 in	Ratio =	0 <180
Max Downward Total Deflection	0.857 in	Ratio =	231 >=120
Max Upward Total Deflection	0.000 in	Ratio =	0 <120

### Maximum Forces & Stresses for Load Combinations

Load Combination	Segment Length	Span #	Max Stress Ratios									Moment Values			Shear Values			
			M	V	C <sub>d</sub>	C <sub>FV</sub>	C <sub>i</sub>	C <sub>r</sub>	C <sub>m</sub>	C <sub>t</sub>	C <sub>L</sub>	M	fb	F'b	V	fv	Fv	
+D+H	Length = 16.50 ft	1	0.340	0.138	0.90	1.200	1.00	1.00	1.00	1.00	0.95	2.18	523.65	1539.42	0.00	0.48	22.32	162.00
+D+L+H	Length = 16.50 ft	1	0.310	0.124	1.00	1.200	1.00	1.00	1.00	1.00	0.94	2.18	523.65	1691.49	0.00	0.48	22.32	180.00
+D+Lr+H	Length = 16.50 ft	1	0.900	0.347	1.25	1.200	1.00	1.00	1.00	1.00	0.91	7.62	1,832.77	2036.82	0.00	1.69	78.12	225.00
+D+S+H	Length = 16.50 ft	1	0.275	0.108	1.15	1.200	1.00	1.00	1.00	1.00	0.92	2.18	523.65	1905.58	0.00	0.48	22.32	207.00
+D+0.750Lr+0.750L+H	Length = 16.50 ft	1	0.739	0.285	1.25	1.200	1.00	1.00	1.00	1.00	0.91	6.26	1,505.49	2036.82	0.00	1.39	64.17	225.00
+D+0.750L+0.750S+H	Length = 16.50 ft	1	0.275	0.108	1.15	1.200	1.00	1.00	1.00	1.00	0.92	2.18	523.65	1905.58	0.00	0.48	22.32	207.00
+D+0.60W+H	Length = 16.50 ft	1	0.218	0.078	1.60	1.200	1.00	1.00	1.00	1.00	0.83	2.18	523.65	2403.56	0.00	0.48	22.32	288.00

Project Title:  
 Engineer:  
 Project ID:  
 Project Descr:

**Wood Beam**

File: ENERCALC.ec6  
 Software copyright ENERCALC, INC. 1983-2020, Build:12.20.8.24  
**TETRA TECH INC**

Lic. # : KW-06002149

DESCRIPTION: **Typical Roof Beam (Before Fire)**

Load Combination	Segment Length	Span #	Max Stress Ratios			Moment Values						Shear Values								
			M	V	C <sub>d</sub>	C <sub>F/V</sub>	C <sub>i</sub>	C <sub>r</sub>	C <sub>m</sub>	C <sub>t</sub>	C <sub>L</sub>	M	fb	F'b	V	fv	Fv			
+D+0.750Lr+0.750L+0.450W+H	Length = 16.50 ft	1	0.626	0.223	1.60	1.200	1.00	1.00	1.00	1.00	0.83	6.26	1,505.49	2403.56	0.00	0.00	0.00	0.00	0.00	288.00
+D+0.750L+0.750S+0.450W+H	Length = 16.50 ft	1	0.218	0.078	1.60	1.200	1.00	1.00	1.00	1.00	0.83	2.18	523.65	2403.56	0.00	0.00	0.00	0.00	0.00	288.00
+0.60D+0.60W+0.60H	Length = 16.50 ft	1	0.131	0.047	1.60	1.200	1.00	1.00	1.00	1.00	0.83	1.31	314.19	2403.56	0.00	0.00	0.00	0.00	0.00	288.00
+D+0.70E+0.60H	Length = 16.50 ft	1	0.218	0.078	1.60	1.200	1.00	1.00	1.00	1.00	0.83	2.18	523.65	2403.56	0.00	0.00	0.00	0.00	0.00	288.00
+D+0.750L+0.750S+0.5250E+H	Length = 16.50 ft	1	0.218	0.078	1.60	1.200	1.00	1.00	1.00	1.00	0.83	2.18	523.65	2403.56	0.00	0.00	0.00	0.00	0.00	288.00
+0.60D+0.70E+H	Length = 16.50 ft	1	0.131	0.047	1.60	1.200	1.00	1.00	1.00	1.00	0.83	1.31	314.19	2403.56	0.00	0.00	0.00	0.00	0.00	288.00

**Overall Maximum Deflections**

Load Combination	Span	Max. "-" Defl	Location in Span	Load Combination	Max. "+" Defl	Location in Span
+D+Lr+H	1	0.8567	8.310		0.0000	0.000

**Vertical Reactions**

Support notation : Far left is #1

Values in KIPS

Load Combination	Support 1	Support 2
Overall MAXimum	1.848	1.848
Overall MINimum	1.320	1.320
+D+H	0.528	0.528
+D+L+H	0.528	0.528
+D+Lr+H	1.848	1.848
+D+S+H	0.528	0.528
+D+0.750Lr+0.750L+H	1.518	1.518
+D+0.750L+0.750S+H	0.528	0.528
+D+0.60W+H	0.528	0.528
+D+0.750Lr+0.750L+0.450W+H	1.518	1.518
+D+0.750L+0.750S+0.450W+H	0.528	0.528
+0.60D+0.60W+0.60H	0.317	0.317
+D+0.70E+0.60H	0.528	0.528
+D+0.750L+0.750S+0.5250E+H	0.528	0.528
+0.60D+0.70E+H	0.317	0.317
D Only	0.528	0.528
Lr Only	1.320	1.320
H Only		



Project Title:  
 Engineer:  
 Project ID:  
 Project Descr:

**Wood Beam**

File: ENERCALC.ec6  
 Software copyright ENERCALC, INC. 1983-2020, Build:12.20.8.24  
**TETRA TECH INC**

Lic. # : KW-06002149

DESCRIPTION: Typical Roof Beam (After Fire) - Assuming 1/2" from all sizes are burned off.

Load Combination	Segment Length	Span #	Max Stress Ratios		C <sub>d</sub>	C <sub>F/V</sub>	C <sub>i</sub>	C <sub>r</sub>	C <sub>m</sub>	C <sub>t</sub>	C <sub>L</sub>	Moment Values			Shear Values			
			M	V								M	fb	F'b	V	fv	Fv	
+D+0.750Lr+0.750L+0.450W+H	Length = 17.0 ft	1	2.066	0.420	1.60	1.200	1.00	1.00	1.00	1.00	0.61	6.65	3,642.02	1762.60	0.00	0.00	0.00	0.00
+D+0.750L+0.750S+0.450W+H	Length = 17.0 ft	1	0.719	0.146	1.60	1.200	1.00	1.00	1.00	1.00	0.61	2.31	1,266.79	1762.60	0.00	0.00	0.00	0.00
+0.60D+0.60W+0.60H	Length = 17.0 ft	1	0.431	0.088	1.60	1.200	1.00	1.00	1.00	1.00	0.61	1.39	760.07	1762.60	0.00	0.00	0.00	0.00
+D+0.70E+0.60H	Length = 17.0 ft	1	0.719	0.146	1.60	1.200	1.00	1.00	1.00	1.00	0.61	2.31	1,266.79	1762.60	0.00	0.00	0.00	0.00
+D+0.750L+0.750S+0.5250E+H	Length = 17.0 ft	1	0.719	0.146	1.60	1.200	1.00	1.00	1.00	1.00	0.61	2.31	1,266.79	1762.60	0.00	0.00	0.00	0.00
+0.60D+0.70E+H	Length = 17.0 ft	1	0.431	0.088	1.60	1.200	1.00	1.00	1.00	1.00	0.61	1.39	760.07	1762.60	0.00	0.00	0.00	0.00

**Overall Maximum Deflections**

Load Combination	Span	Max. "-" Defl	Location in Span	Load Combination	Max. "+" Defl	Location in Span
+D+Lr+H	1	2.8069	8.562		0.0000	0.000

**Vertical Reactions**

Support notation : Far left is #1

Values in KIPS

Load Combination	Support 1	Support 2
Overall MAXimum	1.904	1.904
Overall MINimum	1.360	1.360
+D+H	0.544	0.544
+D+L+H	0.544	0.544
+D+Lr+H	1.904	1.904
+D+S+H	0.544	0.544
+D+0.750Lr+0.750L+H	1.564	1.564
+D+0.750L+0.750S+H	0.544	0.544
+D+0.60W+H	0.544	0.544
+D+0.750Lr+0.750L+0.450W+H	1.564	1.564
+D+0.750L+0.750S+0.450W+H	0.544	0.544
+0.60D+0.60W+0.60H	0.326	0.326
+D+0.70E+0.60H	0.544	0.544
+D+0.750L+0.750S+0.5250E+H	0.544	0.544
+0.60D+0.70E+H	0.326	0.326
D Only	0.544	0.544
Lr Only	1.360	1.360
H Only		

Project Title:  
 Engineer:  
 Project ID:  
 Project Descr:

## Wood Column

File: ENERCALC.ec6  
 Software copyright ENERCALC, INC. 1983-2020, Build:12.20.8.24  
 TETRA TECH INC

Lic. #: KW-06002149

DESCRIPTION: Typical Column (Before Fire)

### Code References

Calculations per NDS 2018, IBC 2018, CBC 2019, ASCE 7-16  
 Load Combinations Used : ASCE 7-16

### General Information

Analysis Method :	Allowable Stress Design			Wood Section Name	4x4	
End Fixities	Top & Bottom Pinned			Wood Grading/Manuf.	Graded Lumber	
Overall Column Height	11 ft			Wood Member Type	Sawn	
<i>( Used for non-slender calculations )</i>						
Wood Species	Douglas Fir-Larch			Exact Width	3.50 in	
Wood Grade	Select Structural			Exact Depth	3.50 in	
Fb +	1,500.0 psi	Fv	180.0 psi	Area	12.250 in <sup>2</sup>	
Fb -	1,500.0 psi	Ft	1,000.0 psi	Ix	12.505 in <sup>4</sup>	
Fc - Prll	1,700.0 psi	Density	31.210 pcf	Iy	12.505 in <sup>4</sup>	
Fc - Perp	625.0 psi					
E : Modulus of Elasticity . . .	x-x Bending	y-y Bending	Axial	Allow Stress Modification Factors		
	Basic	1,900.0	1,900.0	1,900.0 ksi	Cf or Cv for Bending	1.50
	Minimum	690.0	690.0		Cf or Cv for Compression	1.150
					Cf or Cv for Tension	1.50
					Cm : Wet Use Factor	1.0
					Ct : Temperature Factor	1.0
					Cfu : Flat Use Factor	1.0
					Kf : Built-up columns	1.0 NDS 15.3.2
					Use Cr : Repetitive ?	No
Brace condition for deflection (buckling) along columns :						
X-X (width) axis : Unbraced Length for buckling ABOUT Y-Y Axis = 11 ft, K = 1.0						
Y-Y (depth) axis : Unbraced Length for buckling ABOUT X-X Axis = 11 ft, K = 1.0						

### Applied Loads

Service loads entered. Load Factors will be applied for calculations.

Column self weight included : 29.205 lbs \* Dead Load Factor

AXIAL LOADS . . .

DL + LL: Axial Load at 11.0 ft, D = 0.5120, Lr = 1.280 k

### DESIGN SUMMARY

#### Bending & Shear Check Results

<b>PASS</b> Max. Axial+Bending Stress Ratio =	<b>0.3868 : 1</b>
Load Combination	+D+Lr+H
Governing NDS Formlra	Comp Only, fc/Fc'
Location of max. above base	0.0 ft
At maximum location values are . . .	
Applied Axial	1.821 k
Applied Mx	0.0 k-ft
Applied My	0.0 k-ft
Fc : Allowable	384.407 psi

<b>Maximum SERVICE Lateral Load Reactions . .</b>	
Top along Y-Y	0.0 k
Bottom along Y-Y	0.0 k
Top along X-X	0.0 k
Bottom along X-X	0.0 k

<b>Maximum SERVICE Load Lateral Deflections . . .</b>	
Along Y-Y	0.0 in at 0.0 ft above base
for load combination :	n/a
Along X-X	0.0 in at 0.0 ft above base
for load combination :	n/a

<b>PASS</b> Maximum Shear Stress Ratio =	<b>0.0 : 1</b>
Load Combination	+0.60D+0.70E+H
Location of max. above base	11.0 ft
Applied Design Shear	0.0 psi
Allowable Shear	288.0 psi

Other Factors used to calculate allowable stresses . . .

Bending	Compression	Tension
---------	-------------	---------

### Load Combination Results

Load Combination	C <sub>D</sub>	C <sub>P</sub>	Maximum Axial + Bending Stress Ratios			Maximum Shear Ratios		
			Stress Ratio	Status	Location	Stress Ratio	Status	Location
+D+H	0.900	0.215	0.1169	PASS	0.0 ft	0.0	PASS	11.0 ft
+D+L+H	1.000	0.195	0.1161	PASS	0.0 ft	0.0	PASS	11.0 ft
+D+Lr+H	1.250	0.157	0.3868	PASS	0.0 ft	0.0	PASS	11.0 ft
+D+S+H	1.150	0.170	0.1153	PASS	0.0 ft	0.0	PASS	11.0 ft
+D+0.750Lr+0.750L+H	1.250	0.157	0.3188	PASS	0.0 ft	0.0	PASS	11.0 ft
+D+0.750L+0.750S+H	1.150	0.170	0.1153	PASS	0.0 ft	0.0	PASS	11.0 ft
+D+0.60W+H	1.600	0.124	0.1139	PASS	0.0 ft	0.0	PASS	11.0 ft
+D+0.750Lr+0.750L+0.450W+H	1.600	0.124	0.3160	PASS	0.0 ft	0.0	PASS	11.0 ft
+D+0.750L+0.750S+0.450W+H	1.600	0.124	0.1139	PASS	0.0 ft	0.0	PASS	11.0 ft
+0.60D+0.60W+0.60H	1.600	0.124	0.06836	PASS	0.0 ft	0.0	PASS	11.0 ft
+D+0.70E+0.60H	1.600	0.124	0.1139	PASS	0.0 ft	0.0	PASS	11.0 ft
+D+0.750L+0.750S+0.5250E+H	1.600	0.124	0.1139	PASS	0.0 ft	0.0	PASS	11.0 ft

Project Title:  
 Engineer:  
 Project ID:  
 Project Descr:

## Wood Column

File: ENERCALC.ec6  
 Software copyright ENERCALC, INC. 1983-2020, Build:12.20.8.24  
 TETRA TECH INC

Lic. #: KW-06002149

DESCRIPTION: Typical Column (Before Fire)

### Load Combination Results

Load Combination	C <sub>D</sub>	C <sub>P</sub>	Maximum Axial + Bending Stress Ratios			Maximum Shear Ratios		
			Stress Ratio	Status	Location	Stress Ratio	Status	Location
+0.60D+0.70E+H	1.600	0.124	0.06836	PASS	0.0 ft	0.0	PASS	11.0 ft

### Maximum Reactions

Note: Only non-zero reactions are listed.

Load Combination	X-X Axis Reaction		k	Y-Y Axis Reaction		Axial Reaction	My - End Moments		Mx - End Moments	
	@ Base	@ Top		@ Base	@ Top		@ Base	@ Top	@ Base	@ Top
+D+H						0.541				
+D+L+H						0.541				
+D+Lr+H						1.821				
+D+S+H						0.541				
+D+0.750Lr+0.750L+H						1.501				
+D+0.750L+0.750S+H						0.541				
+D+0.60W+H						0.541				
+D+0.750Lr+0.750L+0.450W+H						1.501				
+D+0.750L+0.750S+0.450W+H						0.541				
+0.60D+0.60W+0.60H						0.325				
+D+0.70E+0.60H						0.541				
+D+0.750L+0.750S+0.5250E+H						0.541				
+0.60D+0.70E+H						0.325				
D Only						0.541				
Lr Only						1.280				
L Only										
S Only										
W Only										
E Only										
H Only										

### Maximum Deflections for Load Combinations

Load Combination	Max. X-X Deflection		Distance	Max. Y-Y Deflection		Distance		
	in	ft		in	ft			
+D+H	0.0000	in	0.000	ft	0.0000	in	0.000	ft
+D+L+H	0.0000	in	0.000	ft	0.0000	in	0.000	ft
+D+Lr+H	0.0000	in	0.000	ft	0.0000	in	0.000	ft
+D+S+H	0.0000	in	0.000	ft	0.0000	in	0.000	ft
+D+0.750Lr+0.750L+H	0.0000	in	0.000	ft	0.0000	in	0.000	ft
+D+0.750L+0.750S+H	0.0000	in	0.000	ft	0.0000	in	0.000	ft
+D+0.60W+H	0.0000	in	0.000	ft	0.0000	in	0.000	ft
+D+0.750Lr+0.750L+0.450W+H	0.0000	in	0.000	ft	0.0000	in	0.000	ft
+D+0.750L+0.750S+0.450W+H	0.0000	in	0.000	ft	0.0000	in	0.000	ft
+0.60D+0.60W+0.60H	0.0000	in	0.000	ft	0.0000	in	0.000	ft
+D+0.70E+0.60H	0.0000	in	0.000	ft	0.0000	in	0.000	ft
+D+0.750L+0.750S+0.5250E+H	0.0000	in	0.000	ft	0.0000	in	0.000	ft
+0.60D+0.70E+H	0.0000	in	0.000	ft	0.0000	in	0.000	ft
D Only	0.0000	in	0.000	ft	0.0000	in	0.000	ft
Lr Only	0.0000	in	0.000	ft	0.0000	in	0.000	ft
L Only	0.0000	in	0.000	ft	0.0000	in	0.000	ft
S Only	0.0000	in	0.000	ft	0.0000	in	0.000	ft
W Only	0.0000	in	0.000	ft	0.0000	in	0.000	ft
E Only	0.0000	in	0.000	ft	0.0000	in	0.000	ft
H Only	0.0000	in	0.000	ft	0.0000	in	0.000	ft